

# SURVEY & REMONUMENTATION

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

JOB NUMBER: 94030  
SHEET NO. : 1-443

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 AM 10:55

For corners in

COMMISSION

*Patricia B. Monley*  
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 25W	I-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 1 PAGE 116  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Wednesday, December 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-13: Section Corner common to Sections 34 and 35, T48N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 16" Hemlock N17E, 26 l 30" Hemlock N24W, 10 l	1887: G.P. Cummings describes the Corner as being an iron 5248.4' West of the S.E. Corner of Section 35. No Corner description or accessories are given.  1912: CCI notes corner position on Iron Cliffs easement map dated May, 1912.
---	--

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Found and accepted a 3/4" iron believed to have been set by G.P. Cummings in 1887. Distance West is 2621.52' and distance East is 2628.61'. The Section Corner common to Sections 2 and 3, T47N-R25W is East, 7.92'.

**RATIFIED BY PEER GROUP  
P.A. 845 OF 1990**

*Larry J. Busson*  
DATE Oct. 3, 1994

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Capped the iron, referenced in part "B" above, with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 10" Maple S36E 19.21 ft. Jamros NBT
- 8" Maple N22W 12.35 ft. Jamros NBT
- 8" Maple N76E 45.06 ft. Jamros NBT
- 12" Maple S30W 15.71 ft. Jamros NBT
- Steel sign post South 0.87 ft.

Monument is 0.35' above ground and on Northwesterly slope of steep ridge.  
Bk. 8, Pg. 91



Signed by *Gerald W. Carlson*

Date 12-29-94

Surveyor's Michigan License No. 24589