

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-445

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 AM 10:56

For corners in

COMMISSION

Patricia D. Monley
REGISTER OF DEEDS

	MARQUETTE <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>25W</u>		J-13
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

LIBER 1 PAGE 118
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13: South Quarter Corner Section 35, T48N-R25W. 1844: 1887: G.P. Cummings set an iron at pro-rated distance of William A. Burt's original survey notes describe the corner 2624.2' on-line between the SE and SW Corners of Section monument as a wood post referenced by: 35. No corner accessories given.

10" Hemlock N09E, 28 l
7" Hemlock N40W, 21 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted a 3/4" iron believed to have been set by G.P. Cummings in 1887. Distance West is 2628.61' and distance East is 2625.85'. The found iron is 0.50' South from the straight line between the found SW and SE Corners of Section 35. The North 1/4 Corner Section 2, T47N-R25W is East, 2.59'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**
Larry J. Bussan
DATE Oct. 3, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Capped the iron, referenced in part "B" above, with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

8" White Birch N38E 61.05 ft. Jamros NBT
6" Maple S24E 26.15 ft. Jamros NBT
6" Maple S56W 52.56 ft. Jamros NBT
6" Maple N65W 12.42 ft. Jamros NBT
Steel sign post South 1.2 ft.
Monument is 0.20' above ground.
Bk. 8, Pg. 95



Signed by Gerald W. Carlson Date 12-29-94
Surveyor's Michigan License No. 24589