

JOB NUMBER: 95053
SHEET NO. : 1-615

1995 DEC 27 1995
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 MARQUETTE COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 1995 DEC 27 AM 7:49
Richard L. Woodley

For corners in MARQUETTE (County)	Located In:		Corner Code #
	48N	25W	
1. Public Land Survey	T	R	K-12
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R

LIBER 1 PAGE 29
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

GERALD W. CARLSON Thursday, October 26 95
I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-12: Quarter Corner common to Sections 35 and 36. 1846: cap #25836 established by section line traverse between William Ives' original survey notes describe the corner monument as a wood post referenced by:
10" Elm S63E, 38 l
15" B. Ash N76W, 30 l
1887: George P. Cummings, County Surveyor, in Record of Surveys Pg. 171, indicates the corner as being 2647.3' North of the S.E. Corner of Section 35. No accessories given.
1984: An LCRC recorded by Charles F. Clark RLS #25836, in L. 4, RC Pg. 427, indicates a set 1/2" X 24" rebar and RLS
US-41/N-28 construction centerline station 91+75.04 (MDSHT Proj. 03818) and Southwest Section Corner; placed corner on line 2647.30' Northerly of Section Corner. Referenced by PK nails and metal tags in blazed:
8" Cedar N22E, 17.65'
12" Poplar S45E, 12.82'
12" Poplar S60W, 19.70'
12" Poplar N65W, 45.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1995: Found and accepted a 1/2" Iron with Cap # 25836 & 30091 in good condition as referenced in Part "A" above. Distance West is 5286.77' and Distance South is 2648.71'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**
Oct. 23, 1995
DATE Oct. 23, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1995: Replaced found 1/2" capped Iron with a 2 3/8" O.D. Aluminum Pipe capped with a 3 1/4" Aluminum Tablet Marquette County Survey Monument, 0.1' above ground, and stamped to identify the corner. Repainted old blazed and scribed witness trees:
14" Cedar N22E, 17.64' Existing PK/Washer
7" Poplar S70E, 13.81' Existing PK/Washer
6" Poplar S60E, 19.29' Existing PK/Washer
6" Poplar N62E, 9.34 Existing PK/Washer
Set Green Steel Fence Post w/Yellow Survey Marker Sign North, 1.0'
Bk. 10, Pg. 51



Signed by Gerald W. Carlson Date 11-13-95
24589
Surveyor's Michigan License No. _____