

SURVEY & REMONUMENTATION

JOB NUMBER: 94030
SHEET NO.: 1-448

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:54

For corners in **COMMISSION**

| | | |
|---------------------------------------|-------------------------|---------------|
| MARQUETTE <small>(County)</small> | Located In: | Corner Code # |
| 1. Public Land Survey | T 47N R 25W | L-1 |
| | T 48N R 25W | L-13 ✓ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Patricia A. Manley
REGISTER OF DEEDS

LIBER **1** PAGE **121**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Thursday, December 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|--|--|
| <p>L-13: Quarter Corner common to Section 36, T48N-R25W and Section 1, T47N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:</p> <p>20" Hemlock N35E, 45 l</p> <p>24" Hemlock N62W, 17 l</p> | <p>1880: George P. Cummings survey indicates an iron at the corner with the following distances noted: West, 2623.50' and East, 2623.50'. No corner accessories given.</p> <p>1910: Charles Cummings survey indicates a Corner for commencing a survey in Section 1, T47N-R25W. No corner accessories given. (See Reverse Side).</p> |
|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted DNR monument as referenced by G. Carlson in 1977. Distance West is 2623.41' and distance East to a calculated Township Corner in Lake Superior is 2632.61'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Bassone
DATE Oct. 3, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Found Department of Natural Resources iron pipe with aluminum cap in place referenced by nails in:

| | | | |
|------------------|-------|-----------|-------------|
| 7" Hemlock | S62E | 23.31 ft. | Carlson NBT |
| 11" Maple | S16W | 8.24 ft. | Carlson NBT |
| 8" Maple | N23W | 43.01 ft. | Carlson NBT |
| 15" Yellow Birch | N20E | 33.89 ft. | Carlson NBT |
| Steel sign post | South | 1.35 ft. | |

Monument is stamped MCR 1994 on cap (Marquette County Remonumentation).
Bk. 5, Pg. 141



Signed by *Gerald W. Carlson* Date 12-28-94

Surveyor's Michigan License No. 24589