

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 1999 FEB 12 PM 3:33

For corners in

SECTION 8

<u>MARQUETTE</u> (County)	Located In: Negaunee Township	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>26W</u>	<u>D-05</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Richard L. Manley*  
 REGISTER OF DEEDS

LIBER **R2** PAGE **142**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, George M. Platz, in a field survey on December 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5			●									
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 corner common to: Section 8 T.48N., R.26W.  
 Section 17 T.48N., R.26W.

RATIFIED BY PEER GROUP  
 P.A. 345 OF 1990

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1845: Original US Government Survey by Samuel W. Hill - Set wood post witnessed by:  
 S30°E 10 Links; 18" Hemlock  
 N34°W 10 Links; 8" Y Birch
- 1975: Survey recorded in L.1, P.113, Marquette County Records. Gourdie Fraser & Associates Inc. found a 2" diameter iron with 4" diameter brass cap. Witnessed by:  
 S.45°E. 12.62' 16" W. Birch  
 N.30°E. 12.45' 4" Maple  
 S.30°W. 10.75' 5" Maple

*Yang J. Bussone*  
 DATE 12/15/98

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1 1/2" iron pipe with 4" "paddle style" brass cap. Remaining witnesses from the Gourdie Fraser survey indicate that this point was accepted and used in their 1975 work. A thorough search found no evidence of any other survey monumentation or occupation in the immediate area. No evidence of original B.T.'s could be found. The position of the corner has been used and accepted by others as evidenced by line markings. Original GLO line calls are not distinct enough to verify the position of this corner. All measurements, obtainable recorded survey information and any other obtained unrecorded survey information made available to Spalding DeDecker Associates is documented in the research dossier. Considering the above information, all known evidence favors the correctness of this point.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Accepted Found 1 1/2" iron pipe with 4" "paddle style" brass cap. Stamped "MCR 1998," on brass cap to properly identify accepted corner. Made the following new witnesses:

- Az. 41° 12.47'; Set PK nail w/tag No.38121 in N.W. face of 10" Maple  
 Az. 105° 16.19'; Set PK nail w/tag No.38121 in N. face of 8" White Spruce  
 Az. 151° 11.93'; Set PK nail w/tag No.38121 in W. face of 18" Maple with B.T. tag affixed  
 Az. 215° 10.68'; Set PK nail w/tag No.38121 in N.W. face of 10" Maple



Signed by George M. Platz

Date 12-30-98

Surveyor's Michigan License No. 38121