

SURVEY & REMONUMENTATION

APR 28 1995

JOB NUMBER: 94030
SHEET NO. : 1-517

LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:58

For corners in

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 26W	E-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Patricia A. Monney
REGISTER OF DEEDS

LIBER **1** PAGE **183**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13: Section Corner common to Sections 32 and 33, T48N-R26W. No date given: Survey map recorded in Liber 271, Page 113.
1844: William A. Burt's original survey notes described the corner monument as a 14" Cedar. Referenced by: 10" Lynn, N50W, 21 1
No date given: Old CCI field book indicates Southwest Corner of Section 33 with a distance East of 2611.
Indicates a Section Corner common to Sections 32, 33 and Sections 4 and 5 in the right of way of the railroad nor No corner accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position set 24.42' West of found 1 1/2" iron pipe at Northeast corner of Section 5 on line with the Northeast corner of Section 5 and the found R.R. rail at the South 1/4 Corner of Section 33. Distance West is 2647.48' and distance East is 2629.56'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 5' long, 3/4" diameter rebar capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
5" White Spruce N68W 19.80 ft.
6" White Pine S58W 131.89 ft.
6" White Birch S04E 137.60 ft.
Power Pole S22E 141.10 ft.
Steel sign post N35W 8.25 ft.
Monument is located on an active R.R. grade +/- 1' Northwest of the Northwest rail and is set 1.6' below the bottom of the R.R. rail. Bk. 9, Pg. 15

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Busome
DATE Dec 6, 1994



Signed by Gerald W. Carlson

Date 12-28-94

Surveyor's Michigan License No. 24589