

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

APR 28 1995

JOB NUMBER: 94030
SHEET NO. : 1-519

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:58

For corners in

COMMISSION

Patricia A. Manley
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 26W	F-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 185
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Friday, December 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13: South 1/4 Corner of Section 33, T48N-R26W.
1844: William A. Burt's original survey notes described the corner monument as a wood post referenced by:
16" Cedar, N33E, 16 l
12" Cedar, N28W, 18 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted R.R. rail set by Cummings. Distance West is 2629.56' and distance East is 2628.72'

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Henry J. Bassett
DATE Dec 6, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set 10' long 3/4" iron capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 7" Balsam S44E 95.67 ft.
- 8" Maple S21E 106.29 ft.
- 3 1/2" Maple S03E 133.79 ft.
- 12" Cedar S02W 149.34 ft.

Monument is in flooded area. Cap is just above water which is about 2.0' above mucky bottom.
Bk. 5, Pg. 119



Signed by Gerald W. Carlson Date 12-22-94

Surveyor's Michigan License No. 24589