

**SURVEY &
REMONUMENTATION**

APR 28 1995

JOB NUMBER: 94030

SHEET NO. : 1-521

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:58

Patricia A. Spolney
REGISTER OF DEEDS

For corners in

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 26W	G13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 1 PAGE 187
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13: Section Corner common to Sections 33 and 34, T48N-R26W. 1969: Land Corner Record filed by Ray Brotherton indicates 1844: William A. Burt's original notes described the corner monument as a wood post at the top of hill, referenced by: that 1-1/4" old round iron bar at the Corner common to Sections 33 and 34, T48N-R26W and Section 3 and 4, T47N-R26W. Referenced by:

8" Sugar, N40E, 33 l
10" Sugar, N79W, 10 l

No date given: Old field notes from Cleveland Cliffs Iron Co. indicate the Southeast Corner of Section 33 with a distance West of 2629.34.

6" Sugar, az. 212-1/2, 11.6'
9" Sugar, az. 313, 9.7'

The Corner filed in both Townships is an error because the the original survey notes have double corners at this corner location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted 1 1/2" iron pipe. Distance West is 2628.72' and distance East is 2645.68'. Section Corner common to Sections 3 and 4, T47N-R26W is East, 33.07'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussard
DATE Dec 6, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced a 1 1/2" solid iron with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

8" White Birch S67E 20.59 ft.
5" Maple S30W 11.39 ft. Brotherton NBT
6" Maple N74W 43.12 ft.
9" Birch N51E 4.00 ft.
Steel sign post S36E 1.75 ft.
Monument is 0.5' above ground.
Bk. 6, Pg. 155



Signed by Gerald W. Carlson Date 12-28-94

Surveyor's Michigan License No. 24589