

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030 APR 28 1995
SHEET NO. : 1-523

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:58

For corners in **COMMISSION**

Patricia A. Monley
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>48N</u> R <u>26W</u>	<u>H13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **1** PAGE **189**
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13: South 1/4 Corner Section 34, T48N-R26W.
1844: William A. Burt's original survey notes describe the corner monument as a wood post, referenced by:
9" Fir, N22E, 18 1
10" Fir, N47W, 8 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner position set equidistant and on line between the Southwest and Southeast corners of Section 34. Distances West and East are 2645.685'. The North 1/4 Corner of Section 3, T47N-R26W is East 21.47'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
10" White Pine N70W 21.52 ft.
10" White Spruce N02E 10.18 ft.
12" Red Pine S51E 12.26 ft.
9" Twin Maple S12W 23.79 ft.
Steel sign post N30W 1.74 ft.
Monument is 0.9' above ground and on Easterly side of +/- 20' high hill.
Bk. 9, Pg. 5

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussard
DATE Dec 6, 1994

Signed by *Gerald W. Carlson* Date 12-28-94
Surveyor's Michigan License No. 24589

