

1998 DEC 16 PM 3:19

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>48N</u> R <u>26W</u> | <u>I-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Patricia R. Monney
REGISTER OF DEEDS

LIBER: **R 2** PAGE **64**

Register of Deeds Stamp & File Number

I, KELVIN J. WIXTROM, in a field survey on DECEMBER 7TH, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6: Quarter Corner common to Sections 14 and 15.

1845: Sam U. Hill's original subdivision survey notes describe the corner monument as a wood post referenced by:

14" W. Pine N43E, 04 L 8" Spruce S40W, 18 L

No Date: Section Corner coordinate information from Cleveland Cliffs Iron Company

indicates that they had coordinate information for the corner location. No description of corner monument, accessories, or additional information given.

1990: A Certificate of Survey recorded by Alan K. Pierce, P.S. No. 30097 in L. 001, SM Pg. 656 indicates the corner position as being calculated in the McClure Storage Basin. Distance N00°35'32"W, 2661.48' calculated to a set capped rebar at the Northeast corner of Section 15. Distance S00°35'32"E, 2661.48' calculated to a found brass capped pipe at the Southeast corner of Section 15. No accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6: 1998: Area has been flooded to create the McClure Storage Basin. No evidence of original corner or B.T.'s was found. Established corner position by single proportionate measure between the Northeast corner (I-5) and Southeast corner (I-7) of Section 15 and placed a witness monument on the Section line 319.84' South from the corner. Distance North from I-6 is 2661.34' and Distance South from I-6 is 2661.34'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6: 1998: Set a 3/4" X 36" Re-rod drilled through a large white birch root and concreted in place and capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner for a witness monument to I-6 on the Section line at a distance of 319.84' South of the Quarter Corner I-6. Referenced by:

11" W. Pine S05E, 12.01' 7" Maple S71W, 20.67'
6" Balsam N62W, 5.02' 6" Spruce S75E, 17.96'

Set Green Steel Sign Post w/ Yellow Survey Marker Sign N24W, 2.55'

Note: Bearing trees have d.h. measuring nails set.

T48N R26W and Corner Search Sheet 97559

SCA 97559

RATIFIED BY PEER GROUP
P.A. 245 OF 1990

Larry J. Buasme
DATE Oct 12, 1998



Signed by Kelvin J. Wixtrom

Date 12-15-98

Surveyor's Michigan License No. 32344