

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1998 DEC 16 PM 3: 19

۱ یک قطعہ لایے ہ	Filing Require	ment of Act 74, Mich. P.A. 1	1970
For corners in MARQUETTE (County)	Located In:	Corner Code #	Patricia a. Monlay REGISTER OF DEEDS OF
1. Public Land Survey	T <u>48N</u> R <u>26W</u> T R T R	<u> </u>	
2. Property Controlling in Section	S T R S T R	<u> </u>	- 0 0
3. Miscellaneous	S T R		LIBER ${f R}$ ${f 2}$ page ${f 65}$
Property in Sec.	S T R		Register of Deeds Stamp & File Number
4. Lot No, Recorded Plat			
			- ABCDEFGHIJKLI
	•	•	2 6 5 4 3 2 1-
I, <u>KELVIN J. WIXTROM</u>	, in a field survey on	APRIL 27 TH , 19 98	3
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as			
required in the current manual of survey instructions of the United States Department of the Interior,			
Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of			f " " T T T T T T
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,			. '
recovered, found as express	ed below:		8 19 20 21 22 23 24
	corners, all in the same town an	d range, may be recorded	10 30 29 28 27 26 25
on this certifica	te.		11
	al monument and accessories and		12 31 32 34 35 36
I-7: Section Corner common to Sections 14, 15, 22, and 23. 1845: Sam U. Hill's original subdivision survey notes describe the corner monument as a			
wood post referenced by	:		RATIFIED BY PEER GROUP P.A. 345 OF 1990
10" Sugar \$08\	W, 16 L 15" Sugar	NIGE, OOL	Lany OBusana
1918: C.C.I. survey field notes indicate the corner as a "standard" brass capped monument at the foot of a squared 8" diameter Oak. No accessories given.			
1976-77: A Certificate of Survey by Gourdie, Fraser, and Associates completed in 1976 and recorded in 1977 in L.1, SM Pg. 192 indicates the corner as found. Distance S89-31'-27"E, 1310.86' to a set iron at the N.N.W. 1/16 Corner of Section 23. Referenced by: 7" Oak S75E, 15.35' 18" Oak S20W, 02.12' 7" Oak N02E, 13.28'			
1976-77: An LCRC recordindicates no evidence of 7" R. Oak S75 7" R. Oak N02 (SEE REVERSE SIDE)	original monument or accessories E, 15.35' 18" R. Oa	found. He found a 2" galvaniz	202, and based on a survey from 1976, zed pipe with brass cap 2 ½ above ground.
I-7: 1998: Searched and 2.4' high, and stamped than distances to found revertical position. Checken Checked Line Call: (Sum	to identify the corner. Monument eferences checked reasonably we d Line Call:(Summit of knob, 10.	ner or B.T.'s. Found and accep was set in stones and was lead Il with those recorded by Donr 02 chains [661.32'] East from [1122.00'] East from corner).	oted a 2" O.D. Pipe with a 3 1/4" Brass Cap, ning North 0.4' off of vertical at its top. Bearings nan and Carlson after monument was reset in a corner), Measured call: East 671' to summit. Measured call: East 1095' to Summit. Distance
I-7: 1998: Reset found	ment for corner and accessories of brass capped monument at found sured found references (to set d.h	location in a vertical position,	ing the position of the corner: and stamped it with "MCR 1998". Monument is
21" Oak S25 8" Maple N10	W, 1.55' (Donnan NBT)	8" Oak S77E,	15.67' (Donnan NBT)
Established new reference			CAN
8" Maple S80	W, 4.43'		* KELVIN J.
Green Steel Sign Post w/ Yellow Survey Marker Sign North, 4.50' Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed. WIXTROM PROFESSIONAL SURVEYOR No. 32344			
SCA97559	99 and Corner Search Sheet 9755		ROFESSIONAL
Signed by Kelu	in Q. Wietrom	<u> </u>	-75-98
Surveyor's Michigan Lice		FORM APPROVED BY M	ICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14,1975 REVISED JAN., 1983 REVISED OCT., 1996 PART A CONTINUED:

1980: An LCRC recorded by Gerald W. Carlson P.S. #24589 in L. 4, RC Pg. 19, indicates the corner as a found 2" pipe with brass cap referenced by:
6" Oak S82E, 15.40' (Donnan NBT) 20" Oak S16W, 02.14' (Donnan NBT)
8" Maple North, 13.30' 5" Maple N82W, 20.10'

1990: A Certificate of Survey recorded by Alan K. Pierce P.S. #30097 in L. 001, SM Pg. 656, indicates the corner as a found brass capped pipe as recorded in L. 4, RC Pg. 19. Distance N00-35'-32"W, 5322.96' to a set capped rebar at the N.E. Corner of Section 15. Distance N89-48'-16"W, 2719.65' to a found capped rebar at the South 1/4 Corner of Section 15. No accessories given.