

**SURVEY &  
REMONUMENTATION**

APR 28 1995

JOB NUMBER: 94030  
SHEET NO. : 1-525

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1994 DEC 28 PM 5:58

*Patricia L. Moulton*  
REGISTER OF DEEDS

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>26W</u>	<u>113</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **1** PAGE **191**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, November 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

<p>I-13: Section Corner common to Sections 34 and 35, T48N-R26W. 1844: William A. Burt's original survey notes described the corner monument as a wood post, referenced by: 6" Tamarack, N41W, 136 1 12" Tamarack, N12E, 240 1 No date given: Old field notes from CCI indicates Southeast Corner of Section 34 as an iron, Southeasterly of the rail road tracks. No corner accessories given.</p>	<p>1965: A survey recorded in Liber 72, page 591 by Wayne Claassen, LS #14088, indicates a Corner at the Southwest Corner of Section 35. No corner accessories given. 1992: A Land Corner Recordation Certificate filed by G. Carlson, PS No. 24589. Found R.R. rail on end. Accepted position of R.R. rail. Distances to East agree reasonably close to GLO distances.</p>
---	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Found and accepted railroad rail as referenced in Part A above. Distance West is 5291.37' and distance East is 5268.86'. The Northwest corner of Section 2, T47N-R26W is East 9.96'.

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**

*Larry J. Bussone*  
DATE Nov 7, 1994

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner next to accepted railroad rail, referenced by nails in:  
4" Black Ash S18W 22.73 ft.  
6" White Birch S66W 104.10 ft. Carlson NBT  
5" Maple S74W 64.84 ft. Carlson NBT  
7" White Birch N67E 72.53 ft.  
Steel sign post South 2.0 ft.  
Monument is located at edge of swamp 39' South of centerline South RR rails and 191' East of the Carp River.  
Bk. 7, Pg. 143

Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1993



Record No. 525:

Part "A" Continued:

1992:

Referenced by:

6" Birch, S65W, 104.06'

4" Maple, S73W, 64.94'

Centerline south rail of south set of tracks, N30W, 36.50'

Set cap and iron, (1-1) S87E, 9.90'

Liber 5RC, Page 372.

*Plt 6446  
Geo  
Geo Rem*