

SURVEY & REMONUMENTATION

APR 28 1995

JOB NUMBER: 94030

SHEET NO. : 1-527

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:58

Patricia A. Hendry
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 26W	J-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **1** PAGE **193**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-13: South 1/4 Corner Section 35, T48N-R26W.
1844: William A. Burt's original survey notes describe the corner monument as a wood post, referenced by:
6" Yellow Birch, N75W, 16 l
8" Spruce, S40E, 25 l
1993: Certificate of Survey filed by Larry Bussone, RLS #25833, recorded in Liber 002, Page 69, indicates a found iron at the South 1/4 Corner of Section 35. No corner accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: The corner position established equidistant and on line between the SW and SE Corners of Section 35. Distance West is 2634.43' and distance East is 2634.43'. The N 1/4 Corner of Section 2, T47N-R26W is West 14.21'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussone
DATE Nov 7, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
Power Pole with 2 guy wires N29W 169.11 ft.
First light pole East of building N59E 173.05 ft.
Chiseled 'x' in concrete foundation of building at Southwest corner N08W 194.92 ft.
Punchmark 'x' in steel plate siding of building at Southeast corner N27E 110.35 ft.
Steel sign post North 1.0 ft.
Monument is located on a 7' high flat spoils pile South of and across the road from an abandoned mine building.
Bk. 6, Pg. 119

Signed by Gerald W. Carlson Date 12-22-94
Surveyor's Michigan License No. 24589

