

1998 DEC 16 PM 3:20

*Patricia L. Monley*  
REGISTER OF DEEDS

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE  
(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>48N</u> R <u>26W</u> | <u>K-6</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

LIBER **R2** PAGE **69**

Register of Deeds Stamp & File Number

I, KELVIN J. WIXTROM, in a field survey on OCTOBER 19TH, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

**K-6: Quarter Corner common to Sections 13 and 14.**  
1845: Sam U. Hill's original subdivision survey notes describe the corner monument as a wood post referenced by:  
10" Y. Birch N50E, 08 L 8" Y. Birch S37W, 33 L

1918: C.C.I. survey field notes indicate a blazed 2' Birch at the corner location, and they assumed that it was probably a witness tree. No accessories given.

No Date: Section Corner coordinate information from Cleveland Cliffs Iron Company indicates that they had coordinate information for the corner location. No description of corner monument, accessories, or additional information given.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**K-6: 1998:** Searched and found no evidence of original corner or B.T.'s. Searched location of C.C.I. coordinate indicated in Part A and found no corner. Established corner by single proportionate measure between the Southeast Corner of Section 14 (K-7) and the Northeast corner of Section 14 (K-5). Checked Line Call: (Summit of Ridge, 7.00 chains [462.00'] South from corner); Measured Call: South, 523' to summit. Distance North is 2629.59 and Distance South is 2629.58.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**K-6: 1998:** Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Referenced by:

8" Maple N11W, 1.94' 11" Maple S65E, 29.74'  
8" Maple S06W, 20.70' 8" Maple S55W, 11.00'

Set Green Steel Sign Post w/ Yellow Survey Marker Sign S02W, 2.7'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

T48N R26W, Bk. 3, Pg. 85 and Corner Search Sheet 97559

SCA 97559

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

**RATIFIED BY PEER GROUP**  
**P.A. 945 OF 1990**

*Larry J. Burnham*  
DATE Oct 12, 1998



Signed by Kelvin J. Wixtrom

Date 12-15-98

Surveyor's Michigan License No. 32344