

**COMMISSION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300  
 SHEET NO. : 1-341  
 For corners in

MARQUETTE COUNTY  
 RECEIVED FOR RECORDATION  
 1993 DEC 22 PM 4:15  
 REGISTER OF DEEDS  
 Liber 1 R.C. Page 21  
 Register of Deeds Stamp & File Number

MARQUETTE (County)		Located In:	Corner Code #:
1. Public Land Survey	T 48N R 25W	A-9	
	T 48N R 26W	M-9	
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

I, GERALD W. CARLSON, in a field survey on Monday, December 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35	36					
13											

**A. Description of original monument and accessories and/or subsequent restoration:**

A-9: Section Corner common to Sections 19 and 30, T48N-R25W and Sections 24 and 25, T48N-R26W. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 10" Sugar S75E, 30 1 8" Sugar N36W, 14 1	1940 - Marquette County Road Commission field book #698 indicates the corner of 2" iron pipe with stove poker and a post with the coordinates N3.13, E2613.9. 1979 - C.F. Clark found a 1" iron pipe and nail & tags in 3" Poplar East 24.5 16" Ash S05W 14.28 6" Balsam N15W 36.9 (MDSH US-41 plans, Fed. proj. #F (108) 3; 1953, 56). (See reverse side)
--	--

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 - Found a 1" diameter pipe. The distance to the West 1/4 corner checks with the Plat of Northwoods Lane Acres and the distance to the South checks with 1940 survey of Section 25. within 11.23 ft. The distance to the South 1/4 corner of Section 19 checks relatively close to G.L.O. The bearing South of this corner bears Southeasterly but the crossing of the lake between the next 2 corners could be the reason for misalignment of the bearings as the original G.L.O. surveyors had to offset around the lake. Replaced the 1" diameter pipe with a Marquette County Survey Monument. Peer group ratification 11-29-93.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1993 - Replaced 1" diameter pipe with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

9" Aspen	N07W	6.04 ft.
6" White Birch	S34E	16.90 ft. Clark NBT
8" Aspen	S50W	9.07 ft.
7" Spruce	N70W	18.06 ft. Clark NBT

Bk. 3, Pg. 146



Signed by Gerald W. Carlson Date 12-22-93  
 Surveyor's Michigan License No. 24589

Record No. 341

Part "A" Continued:

Referenced by nails & tags in:

6" White Birch	S40°E	16.88 ft.
20" Ash	S10°W	14.05 ft.
8" Spruce	N82°W	13.09 ft.
8" Dead Balsam	N12°W	36.93 ft.

L1 RC, Pg. 363

*Handwritten notes:*  
#1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100