

1993

JOB NUMBER: 93300
SHEET NO. : 1-344
For corners in

COMMISSIONER LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
RECEIVED POST OFFICE
1993 DEC 22 PM 4:15
Gerald W. Carlson
REGISTERED PROFESSIONAL SURVEYOR

Located In:	Corner Code #
MARQUETTE (County)	
1. Public Land Survey	T 48N R 25W A-12
	T 48N R 26W M-12 ✓
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____

Liber 1 R.C. Page 23.
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, GERALD W. CARLSON, in a field survey on Thursday, December 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12: Quarter Corner common to Section 31, T48N-R25W and Section 36, T48N-R26W. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
 16" Sugar S63W, 20 l
 25" Sugar N70W, 54 l

No date given - Charles Cummings survey indicates the corner, no monument or corner accessories given. His statement in the survey indicates East from West 1/4 corner on transmission line. There is an East/West power line at this corner.
 No date given - The Marquette County Road Commission indicates a old iron pipe at fence corner.
 (See reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 1" iron pipe with 1/2" iron inside with RLS cap 17618. Distance North of this corner checks 1.53 ft. short of Marquette County Road Commission in 1940 and checks 2.78 ft. short of Cummings and check exactly with C.C.I. recent survey. Distance South checks 0.11 ft. short of C.C.I. checks 4.73 ft. short of Cummings. Replaced 1" pipe with 1/2" iron with RLS cap 17618 with Marquette County Survey Monument. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 1" pipe and 1/2" iron RLS cap 17618 with 2 1/8" diameter aluminum pipe capped with 3/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 3rd Power Pole East of road N2 W 23.18 ft.
 4th Power Pole East of road N32E 25.96 ft.
 6" White Pine N80E 57.23 ft.
 4" Poplar S60E 75.10 ft.
 Monument is 0.7 ft. above ground.
 Bk. 3, Pg. 134



Signed by Gerald W. Carlson

Date 12-22-93

Surveyor's Michigan License No. 24589

Record No. 344

Part "A" Continued:

1972 - William Donnan indicates the corner as a found 1 1/2" iron pipe:

Power Pole	N83°W	23.05 ft.
Power Pole	N61°W	50.95 ft.
14" Spruce	S86°E	62.91 ft.

This corner is not recorded.

Handwritten notes:
988
900
100
100
100