

COMMISSION

JOB NUMBER: 93300  
SHEET NO. : 1-392  
For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
RECEIVED FOR RECORDATION  
1993 DEC 29 AM 10:43  
REGISTERED OF DEEDS  
LIBER 1 PAGE 68  
Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 27W T 48N R 27W T R T R T R	E-1 E-12
2. Property Controlling in Section	S T R S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-1: Section Corner common to Sections 4 and 5, T47N-R27W and Sections 32 and 33, T48N-R27W. 1846: Austin Burt's original survey notes describe the corner monument as a Spruce post referenced by:  
8" W.Pine N50.5E, 16 l  
8" Spruce N11W, 31 l

No date given - The Maas coord. system indicates the corner with coordinates N219.03, W26242.11. No description of the monument or corner accessories were given.  
1940 - The North Lake coord. system for Cleveland Cliffs Iron Company indicates the coordinates S43.43 E10584.90. No description of the monument or corner accessories were given. C.C.I. aerial coordinates N205.49, W26228.79.  
(See reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 12" diameter Cummings mushroom in swamp at NW Corner Section 4, T47N-R27W. Left iron mushroom as found. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found 12" diameter cast iron mushroom set by C.P. Cummings in June 1892 with raised letters to identify the corner referenced by nails in:  
11" White Birch N46W 8.82 ft. Wasie NBT  
7" Spruce N30E 39.19 ft.  
7" White Birch S41E 17.75 ft. Wasie NBT  
15" White Birch S19W 17.42 ft. Wasie NBT  
Wasie 12" Spruce N20E 15.7 was found fallen over.  
Bk. 5, Pg. 20



Signed by Gerald W. Carlson Date 12-28-93  
Surveyor's Michigan License No. 24589

Record No. 392

#392  
\$9.00  
7.00  
Burr.

Part "A" Continued:

No date given - The C.C.I. Company triangulation coordinates system indicated the coordinates as N201.52, W26230.43. The corner is indicated marked by a mushroom. No corner accessories given.

No date given - The Marquette County Road Commission field book indicates the corner is an iron mushroom. No corner accessories given.

1978 - Joe Wasie recorded a found cast iron mushroom. This corner is also noted in the Marquette County Road Commission Records.

Referenced by:

14" Birch	N65°W	8.80 ft.
12" Spruce	N20°E	15.71 ft.
6" Birch	S50°E	17.71 ft.

Note: Ties to nails set in witness trees. All bearings are magnetic. 1RC pg. 257.