(a)

For corners in

## SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 197

MARQUE 1	TE t	YTHUG
MIC MIC	HIGA	N
RECEIVED	FOR	RECORE

0						
	1999	NOV	18	PM	2:	05

MARQUETTE (County)	Located In: C	orner Code#
1. Public Land Survey	T <u>48N</u> R <u>27W</u> T R T R T R	<u>H-03</u>

Patricia d. Manley REGISTER OF DEEDS of

S\_\_ T\_\_ R\_\_ S\_\_ T\_\_ R\_\_ S\_\_ T\_\_ R\_\_ 2. Property Controlling in Section 3. Miscellaneous Property in Sec.

LIBER : R2 PAGE 169

Register of Deeds Stamp & File Number

4. Lot No,	Recorded Plat	
5. Private Claims		

I, George M. Platz in a field survey on \_\_December 7 . 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 corner common to:

Section 3

T.48N., R.27W.

Section 10

T.48N., R.27W.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original US Government Survey by Wells Burt - Set wood post witnessed by:
N28°E 11 links; 6" Spruce
S45°W 14 links; 10" Spruce

11

RATIFIED BY PEER GROUP

P.A. 345 OF 1990

12/14/98

1990 - 1993: Various survey sketches, C.C.I. survey information and survey computation sheet for breakdown of Section 10 provided by Glen Van Neste, PS 27464. No description or witnesses given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A thorough search found no evidence of any survey monumentation or occupation in the immediate area. A theoretical position of the corner has been used in the breakdown of section 10 per survey work by Glen Van Neste, PS 27464 and Larry Bussone, PS 25833. The theoretical position of this point is based upon single proportionate measurement, per original GLO notes, between adjacent section corners. No evidence of original B.T.'s could be found. Line calls of the original GLO notes are not distinct enough to verify the position of this point. All measurements, obtainable recorded survey information and any other obtained unrecorded survey information made available to Spalding DeDecker Associates is documented in the research dossier. Considering the above information, we have physically established the 1/4 corner common to sections 3 and 10 by single proportionate measurement, per original GLO notes, between adjacent section corners. corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Marquette County Remonumentation Monument, being a 2 3/8" diameter x 30" aluminum post with 3 1/4" diameter aluminum cap stamped with appropriate corner identification and "1998 PLATZ 38121". Made the following new witnesses:

26.04'; Set mag nail w/tag no.38121 in W. face of 20.55'; Set mag nail w/tag no.38121 in N. face of 5.19'; Set mag nail w/tag no.38121 in S.W. face of 67.86'; Set mag nail w/tag no.38121 in S. face of

W. face of 10" Balsam.
N. face of 12" Tamarac.
W. face of 9" Tamarac w/B.T. tag affixed. Az. 83° Az. 135°

Az. 287° S. face of 14" Tamarac.

signed by Geven M. Plut 7	Date 12-30-98
Surveyor's Michigan License No. 38121	_

REVISED OCT., 1995

<u>A-7:</u>

PART A CONTINUED:

1852: Martin M. Hall's original subdivision survey of T45N-R26W notes describe the monument as a post and add the following reference:

S30W, 27L

Date Unknown: An Easement Map for the Upper Peninsula Power Company, indicates the Southwest comer, no description or references given.

Date Unknown: Marquette County Road Commission notes from field book 643, indicates the corner is an iron pipe and new B.T.s were set. The

following references were given:

Maple

N6OE,

24" White Pine

N68W,

33.7'

Date Unknown: A section breakdown sketch by Gourdie Frasier and Associates, indicates the corner distance S01-01-10E, 2593.85' to a found iron pipe at the West quarter corner of Section 19. It also indicates the corner as being a found 1 1/2" iron pipe with cap.

1978: An LCRC recorded by William R. Donnan, P.S. #17618 in L.1 RC, Pg. 228, indicates the corner as a 1 1/2" O.D. Iron Pipe with stenciled cap.

Referenced by:

30" Dead W. Pine 10" Maple

N76W, S04W,

34.77' 23.90

12.2'

12" Maple 4" Maple N62E. N21W.

12.38 06.53

1978: A Certificate of Survey recorded by Gourdie, Fraser and Associates, Inc., in L. 1 SM, Pg. 231, indicates the corner as a found Iron. Referenced

bv: 10"

Maple

SOAW

23.90

30" W. Pine

N76W,

34.77

4" N21W, 06.531 Maple 12" Maple N62E. 12.38

1990: A Survey Sketch by Sundberg, Carlson and Associates for WEPCO, indicates the Southwest comer. No description or references given.

1990: An Easement Description Map by Sundberg, Carlson and Associates, Inc. for Wisconsin Electric, Liber 130, Pg. 994, indicates the corner distance 1209.92' to the West sixteenth line of Section 18.

1992: A Certificate of Survey recorded by William F. Robey, P.S.# 20711, in L.001 SM, Pg. 707, indicates the corner as a found iron pipe distance S01-00-39E, 2593.73' to the West quarter corner of Section 19. Referenced by:

Maple

N60E.

12.2

24" W. Pine

N68W.

33.7

