

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1999 NOV 18 PM 2:05

For corners in

MARQUETTE (County)	Located In: Ishpeming Township	Corner Code #
1. Public Land Survey	T48N R27W	J-05
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Patricia S. Mosley*  
REGISTER OF DEEDS

LIBER **R2** PAGE **172**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, George M. Platz, in a field survey on December 7, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 corner common to: Section 11 T.48N., R.27W.  
Section 14 T.48N., R.27W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original U.S. Government Survey by Wells Burt - Set wood post witnessed by:  
N74°E 24 Links; 12" Y Birch  
S84°W 25 Links; 13" W Pine

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Busome*  
DATE 12/15/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A thorough search found no evidence of any survey monumentation or occupation in the immediate area. No evidence of original B.T.'s could be found and line calls of the original GLO notes are not distinct enough to locate this point. No recorded survey information exists in the Marquette County Register of Deeds and no unrecorded survey information could be obtained regarding this corner. Considering the above information, we have physically established the one-quarter corner common to Sections 11 and 14 by single proportionate measurement. Orientation and measurement between this calculated location and adjacent section corners fit reasonably well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Marquette County Remonumentation Monument, being a 2 3/8" diameter x 30" aluminum post with 3 1/4" diameter aluminum cap stamped with appropriate corner identification and "1998 PLATZ, 38121". Made the following new witnesses:

Az. 228° 8.22'; Set mag nail w/tag No.38121 in E. face of 7" Maple.  
Az. 248° 19.64'; Set mag nail w/tag No.38121 in N.W. face of 8" Spruce.  
Az. 278° 19.23'; Set mag nail w/tag No.38121 in N. face of 5" Spruce.  
Az. 356° 2.11'; Set mag nail w/tag No.38121 in E. face of 18" Spruce w/B.T. tag affixed.



Signed by George M. Platz

Date 12-30-98

Surveyor's Michigan License No. 38121