

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300
SHEET NO. : 1-385

For corners in

MARQUETTE
(County)

Located In:

Corner Code ##

- 1. Public Land Survey

T	47N	R	27W	L-1
T	48N	R	27W	L-13
T		R		
T		R		
- 2. Property Controlling in Section

S		T		R	
S		T		R	
- 3. Miscellaneous Property in Sec.

S		T		R	
S		T		R	
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

MARQUETTE COUNTY
 RECEIVED FOR RECORD
 1993 DEC 30 PM 1:09
 GERALD W. CARLSON
 REGISTERED PROFESSIONAL SURVEYOR

LIBER 1 PAGE 92
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1: Quarter Corner common to Section 1, T47N-R27W and 1940 - Cleveland Cliffs Iron Company records indicate a Section 36, T48N-R27W. 1846: Austin Burt's original survey standard corner with coordinates N76.88, W7687.26. No notes describe the corner monument as a wood post corner accessories given.

referenced by:
 16" Birch N51E, 17 l
 10" Maple N39W, 15 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - The corner was set proportional distance and on line between the NW and the NE corner of Section 1, T47N-R27W. Distance West and East is 2650.085' which is 0.10' longer than C.C.I. triangulation coordinate distances. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 4" Oak S42E 13.27 ft.
- 19" Oak N44W 43.83 ft.
- 5" Maple N06W 33.96 ft.
- 5" Maple N19E 42.08 ft.

Bk. 4, Pg. 95



Signed by Gerald W. Carlson

Date 12-29-93

Surveyor's Michigan License No. 24589