

JOB NUMBER: 95053
SHEET NO. : 1-651

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Located In:

Corner Code #

MARQUETTE (County)

1. Public Land Survey

T48N R27W

M-6 ✓

T48N R26W

A-6

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Section

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECEIVED FOR RECORD
1995 DEC 27 AM 7:49
MARQUETTE COUNTY
MICHIGAN
REGISTER OF DEEDS
Dustin A. Woodbury

LIBER 1 PAGE 29
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, GERALD W. CARLSON, in a field survey on Friday, December 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6: Quarter Corner common to Section 13, T48N-R27W and Section 18, T48N-R26W. 1844: Austin Burt's original survey notes describe the corner as a wood post referenced by:
 14" Sugar S43W, 34 l
 14" Sugar N65W, 13 l
 1992: A Certificate of Survey recorded by Larry J. Bussone RLS #25833, in L. 002, SM Pg. 17, indicates the corner as a set 1/2" Iron Pin recorded in Marquette Co. Rec. Cor. Book. No accessories given.
 1993: An LCRC recorded by Larry J. Bussone RLS #25833, in L. 5, RC Pg. 375, indicates that Marquette Co. road data showed this corner in C/L of County Road. Local resident placed corner in road opposite fence line South. Survey ties to NE and SE Corners Section 13 confirmed C/L road and intersection of fence line placement. Bussone set a 1/2" Iron and Cap at this location. Established references with upper and lower notches in trees: (See Reverse Side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1/2" Iron with damaged Yellow Cap, 0.5' below gravel road at C/L. Distance North is 2628.62' and Distance South is 2625.82'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE 12/04/95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found 1/2" iron with a 3/4" X 24" xerod capped with a 3 1/4" aluminum tablet Marquette County Survey Monument, 0.53' below ground at C/L Krooks Road, and stamped to identify the corner. Measured to existing references using set duplex nails in:

- 18" Maple N08W, 43.53' (Bussone N.B.T.)
- 8" Maple N57E, 29.77' (Bussone N.B.T.)
- 8" Maple S35E, 41.90' (Bussone N.B.T.)
- 10" Maple S13W, 34.37' (Bussone N.B.T.)
- Green Steel Sign Post w/Survey Marker Sign N11E, 19.73'

Note: Placed blank B.T. Tag over monument to protect it. Bearing trees have face and butt blazes, paint, and B.T. Tags affixed.

Bk. 10, PP. 61-62.

Signed by *Gerald W. Carlson*

Date 12-20-95

Surveyor's Michigan License No. 24589

Record N0. 651:

Part A Continued:

11" Maple	S09W,	34.1'
6" Maple	S39.5E,	41.5'
7" Maple	N51E,	29.4'
16" Maple	N12W,	43.0'

Handwritten notes:
11" Maple
6" Maple
7" Maple
16" Maple