

APR 1 1986

JOB NUMBER: 950S3
SHEET NO. : 1-654

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1995 DEC 27 AM 7:50
REGISTER OF DEEDS
*Robert D. M...
m*

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey	T ^{48N} _____ R ^{27W} _____	M-9 ✓
	T ^{48N} _____ R ^{26W} _____	A-9
	T _____ R _____	
	T _____ R _____	
2. Property Controlling	S _____ T _____ R _____	
in Section	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	
Property in Section	S _____ T _____ R _____	

LIBER 1 PAGE 29
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Monday, December 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9: Section Corner common to Sections 24 and 25, T48N-R27W 1940: B. Schjonberg in MCRC F.B. #701 indicates the corner and Sections 19 and 30, T48N-R26W. 1844: Austin Burt's original survey notes describe the corner monument as a wood post referenced by:
8" Sugar S33W, 66 l
7" Sugar N66W, 45 l
No Date: The corner is shown on an unidentified map recorded in L. 328, Deeds Pg. 324.
No Date: MCRC F.B. #654 indicates the corner as a Square Wooden Stake.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1" O.D. Iron Pipe, 1.33' above ground, next to a 4' high Squared Wooden Post. Distance North is 2630.30' and Distance South is 2624.95'.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" aluminum tablet Marquette County Survey Monument over the top of found 1" iron pipe, 1.0' above ground, and stamped to identify the corner. Established references using set duplex nails in found N.B.T.'s, and a set duplex nail in a newly established N.B.T.:

13" Poplar	S03W,	19.81' (Found N.B.T.)
9" Maple	S27W,	32.45'
10" Maple	N85W,	26.45' (Found N.B.T.)
7" Maple	N30W,	20.69' (Found N.B.T.)
Green Steel Sign Post w/Survey Marker Sign	N66E,	1.71'

Note: Bearing trees were face and butt blazed, painted, and had B.T. Tags affixed.
Bk. 10, PP. 67-68.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. ...
DATE 12/04/95



Signed by Gerald W. Carlson

Date 12-20-95

Surveyor's Michigan License No. 24589