

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>49</u> N. R. <u>26</u> E.		<u>F3, G3</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 28, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner F3: Original monument and accessories not found. Found rebar with RLS Charles Clark cap.**
- Corner G3: Original monument and accessories not found. Found 3" iron pipe purported to have been set by Charles Cummings**
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner F3: Restored at Charles Clark corner.**
- Corner G3: Restored at 3" pipe.**
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner F3: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.**  
 PK Nail in 5" maple N60W 9.59' S, NBT  
 PK Nail in 4" maple N40E 5.51' S, NBT  
 PK Nail in 5" maple S15E 4.00' S, NBT
- Corner G3: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.**  
 4" maple S12W 10.4' S9, NBT  
 3" maple N74W 4.8' S4, NBT  
 5" sugar N33E 14.2' S3, NBT  
 3" pipe 6' above ground for marker

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-28-85

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006