

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Marquette County

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>49</u> N. S., R. <u>26</u> W.	<u>E4, E3, F5</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 22, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E4: Original monument and accessories not found

Corner E3: Found old iron pipe with cap marked $\frac{5}{4}$ on record at Marquette County Road Commission.

Corner F5: Original Monument and accessories not found

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E4: Restored midway and on line between section corners north and south.

Corner E3: Restored at pipe

Corner F5: Restored midway and on line between section corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E4: Set 1" I.D. by 32" I.P. with 4" aluminum cap.

10" Cedar S01E, 39.8', $\frac{1}{4}$ s, NBT
 10" Sugar S56W, 14.9', $\frac{1}{4}$ s, NBT
 12" Sugar N45E, 12.3', $\frac{1}{4}$ s, NBT

Corner E3: Found iron pipe with cap marked $\frac{5}{4}$ on record at Marquette County Road Commission.

7" maple N04E 23.4'
 6" balsam S53E 16.5'
 10" maple S55W 39.9'

Corner F5: Set 1" I.D. by 32" I.P. with 4" aluminum cap.

9" Y.Birch N27W 5.2' $\frac{1}{4}$ s, NBT
 5" Sugar N80E 16.5' $\frac{1}{4}$ s, NBT
 4" Sugar S10E 18.8' $\frac{1}{4}$ s, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-28-85

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006