

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Marquette County	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> <sup>N.</sup> / <sub>S.</sub> , R. <u>26</u> <sup>E.</sup> / <sub>W.</sub>	<u>I3, H3, E5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S., R. _____ E. _____ S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S., R. _____ E. _____ S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**Corner I3: Original monument and accessories not found. 2" I.D. by 60" high iron pipe found.**  
**Corner H3: Original monument and accessories not found. Found 2" I.D. by 60" high iron pipe.**  
**Corner E5: Original monument and accessories not found.**

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**Corner I3: Restored 12-12-84 at iron pipe**  
**Corner H3: Restored 12-12-84 at iron pipe**  
**Corner E5: Restored 1-16-85 by double proportion between corners and land calls.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**Corner I3: 2" I.D. by unknown length Iron Pipe 60" high. 8" Maple S70E 14.00'**  
**Nail and RLS tag 20711 in witnesses 7" Maple N17E 18.10'**  
**13" Maple N50W 14.30'**  
**10" Y. Birch S29W 20.75'**  
**Corner H3: 2" I.D. by unknown length Iron pipe 60" high. 7" sugar N06E 17.7' 1/2 S, NB'**  
**8" Sugar S46E 17.9' 1/2 S, NB'**  
**5" Sugar N66W 25.4' 1/2 S, NB'**  
**Corner E5: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 4" Sugar S44E 13.1' S16, I'**  
**4" Maple N56E 24.6' S9, N'**  
**5" Sugar S34W 22.8' S17, N'**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-28-85

CHIEF OF SURVEY PARTS  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006