

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. R. <u>26</u> W.	<u>D3, C2, G2</u>
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. <u>49</u> N. R. <u>26</u> W.	<u>7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 25, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D3: Original monument and accessories not found

Corner C2: Original monument and accessories not found

Corner G2: Found 2" I.D. by 4" I.P. in concrete recorded by Marquette Co. Road Commission.

Corner 7: Found 2" I.D. by 48" I.P. in concrete.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D3: Restored midway and on line between section corners east and west, fits with land calls.

Corner C2: Restored midway and on line between section corners north and south.

Corner G2: Restored at Iron Pipe.

Corner 7: Established at Iron Pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D3: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 8" Hemlock S10W 7.0' 1/2S, NE

20" Cedar S40E 35.8' 1/2S, NE

24" Hemlock North 11.2' 1/2S, NE

Corner C2: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 4" Sugar S70W 10.0' 1/2S, NBT

7" Maple S74E 19.5' 1/2S, NBT

5" Sugar N20W 39.5' 1/2S, NBT

Corner G2: Found 2" I.D. by 48" I.P. in concrete. 8" Sugar S25E 10.0'

7" Sugar N24E 14.2'

10" Sugar N38W 10.2'

Corner 7: Found 2" I.D. by 48" I.P. in concrete. 14" Sugar N45W 4.9'

Gate post S45E 2.2'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (REAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-28-85

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006