

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Marquette County		LOCATED IN-:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. 8. R. 26 W.		G5, G4
2. PROPERTY CONTROLLING IN SECTION	T. 49 N. 8. R. 26 W.		14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.		
4. LOT NO. _____	, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 17, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner G5: Original monument and accessories not found.

Corner G4: Original monument and accessories not found.

Corner 14: Not set on original survey or subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G5: Restored from corners north and west and land calls south and east. Corner falls on north face of high rock hill.

Corner G4: Restored midway and on line between corners north and south.

Corner 14: Established midway and on line between 1/4 corner north and section corner south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G5: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 5" maple S15E 22.0' S15, NBT
 4" maple N81E 21.6' S10, NBT
 7" oak N02W 13.0' S9, NBT

Corner G4: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 4" maple S24W 21.6' 1/2S, NBT
 4" maple S40E 18.5' 1/2S, NBT
 4" spruce N58E 11.8' 1/2S, NBT

Corner 14: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 9" sugar S20E 16.4' 1/16S, BT
 5" Sugar S34W 14.1' 1/16S, BT
 11" sugar N20E 22.5' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-22-85

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006