

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Marquette County

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>4</u> .T. <u>49</u> N. <u>26</u> E. _____ S. _____ R. _____ W. _____		<u>16, 16A</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 28, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 16: Not set on original survey. Found rebar set by Charles Clark.

Corner 16A: This corner is midway and on line between corners 16 and G3. Found old fence corner S72W 50ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 16: Restored at Charles Clark rebar.

Corner 16A: This corner established midway and on line between corners 16 and G3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 16: Set 1" I.D. by 32" iron pipe over Charles Clark rebar.

12" oak N29E 9.5' 1/16S, BT
 8" maple N67W 6.4' 1/16S, BT
 9" maple S04W 1.1' 1/16S, BT

Corner 16A: Set 1" I.D. by 32" iron pipe with 4" aluminum cap.

10" sugar S75E 29.5' 1/64 S, BT
 7" sugar S17W 20.8' 1/64 S, BT
 5" sugar N63W 10.1' 1/64 S, BT
 9" sugar squared S66W 2.7'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-20-85

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET

RECEIVED
 FEB 11 1985
 WATER MANAGEMENT