

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. S., R. <u>27</u> E. W.	<u>E-5, E-6, E-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 4 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- E-5 N.W. Section corner - Sec. 16; 3/4" pipe - Set by Co. Rd. Comm. - 1948; Sugar 11" - S5°W - 2.8'; Sugar 14" - N75°W - 16.7'
 - E-6 West 1/4 corner - Sec. 16; 3/4" pipe - Set by Co. Rd. Comm - 1948; W. Birch 6" - S43°E - 47.2'; J. Pine 5" - S9°W - 107.3'
 - E-7 S.W. Section corner - Sec. 16; Iron pipe; Jack pine 4" - N68°E - 29.6'; Jack Pine 7" - S28°E - 22.7; Witnessed by Marquette Co. Rd. Comm. April 30, 1948.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- E-5 Found 3/4" pipe set by Co. Road Comm. witness in place in good condition.
 - E-6 Set M.P.O.L. between the N.W. and S.W. section corners of Sec. 16. 3/4" pipe S42°W - 62.53' from this point - Said to have been set M.P.O.L. by Co. Rd. Comm. in 1948 but misplaced because of errors in their computation.
 - E-7 Found 1 1/2" pipe - old (1948) Co. Rd. Comm. witness in place. S.E. one has been cut.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ALL - 1" pipe, 4" aluminum cap
 - E-5 6" Maple - N80°E - 12.6'; 19" Y. Birch - S15°W - 30.65'; 13" Maple - S15°W - 2.6' (old Co. Rd. Comm. Wits.); 18" Maple - N63°W - 16.5' (Old Co. Rd. Comm. Wits.).
 - E-6 8" J. Pine - N41°W - 12.1'; 10" J. Pine - N61°E - 13.0'; 8" J. Pine - S12°E - 16.2'; 9" J. Pine - S45°W - 45.9'.
 - E-7 8" J. Pine - N24°W - 53.15'; 6" J. Pine - N33°E - 21.3'; Old Co. Rd. N.B.T. 6" J. Pine - N68°E - 29.4'; 6" J. Pine - S38°E - 31.2'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 11-6-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558