

LANSING

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. S., R. <u>27</u> E. W.	<u>G-4, G-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 6 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 G-4 East  $\frac{1}{4}$  corner - Section 9; Wood Post - G.L.O.; Cedar 8" - N64°E - 11 lks.; Cedar 16" - S69°W - 14 lks.

G-5 S.E. Section Corner - Section 9; Pipe - set by R.J. Brotherton R.L.S. for C.C.I. No record of N.B.T.'s

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 G-4 Found 4"x4" sq. cedar post roots of S.W. O.B.T. and partial stump of N.E. O.B.T. in place. Trunk of fallen S.W. O.B.T. lies down slope about 8'.

G-5 Replaced 3/4" pipe set by John Brotherton R.L.S. with our monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 G-4 1" pipe, 4" aluminum cap & Cedar post beside monument.  
 5" W. Pine - N40°W - 19.0'; 6" W. Pine - N55°E - 8.8'; 6" Spruce - S54°E - 17.75';  
 4" Cedar - S69°W - 16.7'

G-5 1" pipe, 4" aluminum cap; 9" W. Pine - N6°E - 19.0'; 6" W. Pine - N89°E - 77.3';  
8" J. Pine - S12°E - 49.45'; 5" J. Pine - S67°W - 26.7'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE 11-6-78 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558