

# LAND CORNER RECORDATION CERTIFICATE

LAANSING

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>49</u> N. S., R. <u>27</u> E. W.	<u>6G, 7G, F-6</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on September 21 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 6G - East ¼ corner - Section 16; Wood Post - G.L.O.; Spruce 10 - S48°E - 12½ lks.; SP. Pine 10 - N46°W - 28 lks.
- 7G - S.E. Section corner - Sec. 16; pipe set by R.J. Brotherton R.L.S. for C.C.I.; W.P. Stp. 32" - N43°E - 11.5'; W.P. Stp. 28" - S31°E - 15.0'
- F-6 - Center of Sec. 16; ¾" Pipe - set by Co. Rd. Comm., -1948; J. Pine 3" - S68°W - 31.2'; J. Pine 6" - S89°E - 40.4'

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- 6G - Set M.P.O.L. between the N.E. and S.E. section corners of Sec. 16.
- 7G - Found ¾" pipe - R.J. Brotherton N.B.T.'s in place - replaced with D.N.R. monument.
- F-6 - Set at intersection of N-S and E-W ¼ lines. ¾" pipe found S64°W - 83.27' from this point - set by Co. Rd. Comm. in 1948 but because of errors in their computations and improper methods it was not correctly placed.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL - 1" pipe, 4" aluminum cap
- 6G - 6" J. Pine - N36°E - 89.10'; 5" J. Pine - N56°E - 74.68'; 6" J. Pine - S85°E - 103.55'; 6" J. Pine - S15°E - 126.90'
  - 7G - 8" W. Pine - S73°W - 25.90'; 4" W. Pine - N34°W - 43.10'; 4" W. Spruce - N05°W - 29.15'; 3" W. Spruce - S54°E - 21.25'
  - F-6 - 6" J. Pine - S89°W - 15.05'; 5" J. Pine - S20°W - 9.0'; 9" J. Pine - N79°E - 20.5'; 6" J. Pine - N15°W - 23.5'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 11-6-78  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558