

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Marquette

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. S., R. <u>27</u> E. W.	<u>F-5, F-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>49</u> N. S., R. <u>27</u> E. W.	<u>14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 21 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

F-5 - North $\frac{1}{4}$ corner - Sec. 16; Wood Post - G.L.O.; W. Pine 34" - N26°E - 34 lks.;
Y. Birch 12" - S6°W - 43 lks.

F-7 - South $\frac{1}{4}$ corner - Sec. 16, ~~not previously established~~

14 - S 1/16 corner on the east section line - Sec. 16; not previously established

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-5 - Set M.P.O.L. between the N.E. and N.W. section corners of Sec. 16. Fits calls to rock ledge west.

F-7 - Set M.P.O.L. between the S.W. and S.E. section corners of Sec. 16. 3/4" pipe found S71°W - 97.97' from this point - set by Co. Rd. Comm. in 1948 but because of errors in their computations and improper methods it was not correctly placed.

14 - Set M.P.O.L. between the east $\frac{1}{4}$ corner and the S.E. section corner of Sec. 16

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ALL - 1" pipe, 4" aluminum cap

F-5 - 8" Balsam - S32°W - 19.7'; 8" Birch - N3°W - 12.2'; 6" Spruce - N64°E - 32.2';
4" Poplar - S59°E - 8.3'

F-7 9" J. Pine - N87°E - 1.05'; 8" J. Pine - N1°E - 9.2'; 4" J. Pine - N75°W - 22.45';
Old Blazes and scribing - 12" J. Pine - S71°W - 111.2'

14 - 9" J. Pine - S23°E - 6.43'; 2" J. Pine - S67°W - 51.00'; 3" J. Pine - N36°W - 38.75';
8" J. Pine - N76°E - 24.75'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt DATE 11-6-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558