

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1999 NOV 18 PM 2:05

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

<u>MARQUETTE</u> (County)	Located in: Ishpeming Township	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>27W</u>	D-01
	T <u>49N</u> R <u>27W</u>	D-13 ✓
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

Patricia A. Marley
REGISTER OF DEEDS

LIBER **R2** PAGE 167
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George M. Platz, in a field survey on December 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 corner common to: Section 5 T.48N., R.27W.
Section 32 T.48N., R.27W.

A	B	C	D	E	F	G	H	I	J	K	L	I
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1846: Original US Government Survey by Austin Burt 1846. Set wood post witnessed by:
N76°E 23 Links; 7" Spruce
N48°W 13 Links; 10" Spruce

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Bussard
DATE 12/14/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A thorough search found no evidence of any survey monumentation or occupation in the immediate area except for a ver old paint line running north/south and a broken fence running east west for about 100' in the general area. No evidenc of original B.T.'s could be found. No recorded survey information exists in the Marquette County Register of Deeds. N unrecorded survey information has been made available to Spalding DeDecker Associates. Any relevant GLO line calls wer forever changed by the flooding of the Dead River Basin. All measurements, obtainable recorded survey information an any other obtained unrecorded survey information made available to Spalding DeDecker Associates is documented in th research dossier. Considering the above, we have physically established the 1/4 corner common to sections 5 and 32 b single proportionate measurement, per original GLO notes, between adjacent section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Marquette County Remonumentation Monument, being a 2 3/8" diameter x 30" aluminum post with 3 1/4" diamete aluminum cap stamped with appropriate corner identification and "1998 PLATZ 38121". Made the following new witnesses:

- Az. 98° 8.33'; Set mag nail w/tag No. 38121 in S.W. face of tree.
- Az. 137° 12.39'; Set mag nail w/tag No. 38121 in N.E. face of a 7" White Pine w/B.T. tag affixed.
- Az. 180° 5.83'; Set mag nail w/tag No. 38121 in E. face of a 6" White Pine.
- Az. 297° 8.97'; Set mag nail w/tag No. 38121 in S. face of a 8" Jack Pine.



Signed by George M. Platz

Date 12-30-98

Surveyor's Michigan License No. 38121