

1993

COMMISSION

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

JOB NUMBER: 93300 SHEET NO. : 1-327 For corners in

LAND CORNER RECORDATION CERTIFICATE 1993 DEC 22 PM 4:12 Filing Requirement of Act 74, Mich. P.A. 1970

Patricia L. Marley REGISTERED PROFESSIONAL SURVEYOR 10

Table with columns: Located In: (MARQUETTE County), Corner Code #, and survey details (Public Land Survey, Property Controlling, etc.)

Liber 1 R.C. Page 2

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, GERALD W. CARLSON, in a field survey on Tuesday, November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13: South Quarter Corner Section 31. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 5" Y.Pine N68W, 24 1; 5" Y.Pine N21E, 21 1. 1987 - G. Carlson set a 5/8 rerod with RLS cap #24589 equidistant and online between the SW & SE corners of Section 31 referenced by: 12" Red Pine N50W 5.44 ft.; 8" Red Pine S78E 28.49 ft.; 6" Red Pine S31E 28.22 ft.; 6" Aspen S10W 16.02 ft. LS RC, Pg. 160

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - During recent remonumentation survey the corner was found to be 0.90 ft. West of monumented position in 1987 because of 1.7 ft. error in traverse calculation. The corner was correctly monumented equidistant and on line between the SW and SE corners of Section 31. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in: 12" Red Pine N43W 12.65 ft.; 10" Red Pine S74E 29.42 ft.; 8" Red Pine S42E 28.96 ft.; 4" Balsam S41W 22.81 ft. 0.50' above ground. Bk. 3, pg. 104



Signed by Gerald W. Carlson Date 12-22-93

Surveyor's Michigan License No. 24589