

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-326
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORDING
MARQUETTE COUNTY
MICHIGAN
1993 DEC 22 PM 4:14
Liber 1 R.C. Page 18.
Register of Deeds Stamp & File Number

Located In:	Corner Code #
MARQUETTE (County)	
1. Public Land Survey T 49N R 25W	C-13
T R	
T R	
T R	
2. Property Controlling in Section S T R	
S T R	
3. Miscellaneous Property in Sec. S T R	
S T R	
4. Lot No. , Recorded Plat	
5. Private Claims	

I, GERALD W. CARLSON, in a field survey on Tuesday, November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-13: Section Corner common to Sections 31 and 32, T49N- R25W. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
 12" Aspen N80W, 31 1
 8" W.Pine N35E, 25 1
 1936 - Marquette County Road Commission indicates a cedar post in a very old mound of stones. No corner accessories given.
 1988 - G. Carlson found a 5/8" rerod and LS cap #17618 loose in rock pile and remains of old wood post. Position checked well with original government notes and also the 1936 Marquette County Road Commission notes. Drilled and grouted iron into rock. (See reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron with RLS cap # 17618 placed Marquette County Survey Monument stamped to identify the corner on top of iron. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - 3 1/4" diameter aluminum table Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 16" White Pine N75W 15.70 ft. Carlson NBT
 16" White Pine N27W 22.45 ft. Carlson NBT
 10" Maple S55E 21.90 ft. Carlson NBT
 9" Maple S33W 17.42 ft. Carlson NBT
 Corner is 0.2 ft. above ground surrounded by rocks.
 Bk. 3, pg. 96



Signed by Gerald W. Carlson
Surveyor's Michigan License No. 24589

Date 12-22-93

Record No. 326

Part "A" Continued:

Referenced by:

13" White Pine	N30W	22.31 ft.
12" White Pine	N78W	15.78 ft.
8" Maple	S29W	17.50 ft.
10" Maple	S50E	21.90 ft.
L5 RC, Pg. 160		

2839
900
900
900