

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300

SHEET NO. : 1-325

For corners in

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 25W	D-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY
 RECEIVED FOR RECORDATION
 1993 DEC 22 PM 4:14
 REGISTERED IN 1993
 70

Liber 1 R.C. Page 17.

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	P
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13: South Quarter Corner Section 32, 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
 7" Aspen N50W, 18 1
 8" Y.Pine N24E, 24 1

1936 - Marquette County Road Commission's notes indicate a circular iron pin inside an old iron pipe about 19 ft. Westerly of the LS&I Railroad referenced by:
 8" Poplar S46W 34.6 ft.
 5" Maple S06E 37.8 ft.
 (See reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron with G. Carlson LS cap. Replaced with 2 1/8" diameter aluminum pipe with 3 1/4" diameter aluminum tablet Marquette County Survey Monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 4" Maple N40E 25.27 ft.
 6" Poplar S50W 12.94 ft.
 3" Tag Alder N73W 15.25 ft.
 4" Poplar N4W 40.03 ft.
 0.7 ft. above ground.
 Bk. 3, pg. 88



Signed by Gerald W. Carlson
 Surveyor's Michigan License No. 24589

Date 12-22-93

Record No. 325

At 1988
9.00
12.00
12.00

Part "A" Continued:

1988 - G. Carlson found and old pipe set by County Road Commission disturbed and out of position. Set a 5/8 rerod with RLS cap No. 24589. Equal distance and on line between the Southwest and Southeast corners of Section 32. 33.4 ft. West of the centerline of the old railroad grade referenced by:

6" Maple	N20E	14.24 ft.
16" Red Pine	S47W	21.95 ft.
6" White Birch	N67W	20.01 ft.
4" Maple	N25W	18.26 ft.
L5 RC, Pg. 160		