

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300

SHEET NO.: 1-324

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T 49N R 25W	E-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY
RECEIVED FROM
1993 DEC 22 PM 4:14
Liber 1: R.C. Page 16
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, GERALD W. CARLSON, in a field survey on Tuesday, December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13: Section Corner common to Sections 32 and 33, T49N- 1936 - MCRC F.B. 727, indicates circ. iron pin set 76.7'
R25W. 1845: William A. Burt's original survey notes Westerly of iron pipe incorrectly set by someone. Referenced describe the corner monument as a wood post referenced by: by:
8" Y.Pine N23W, 51.1 7" J.Pine N44W, 27.1'
6" Spruce N39E, 29.1 12" J.Pine N13W, 17.2'

See reverse side for additional information.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 3/4" field bar as noted in 1988 G. Carlson LCRC and placed a 3/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner on top of the existing field bar.
Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner on top of a found 3/4" diameter steel bar referenced by nails in:
19" Red Pine N05E 25.95 ft. Carlson NBT.
5" Maple S50E 15.54 ft. Carlson NBT.
13" Red Pine S25E 28.99 ft. Carlson NBT.
8" Twin Maple N73W 9.93 ft. Carlson NBT.
11" above ground.
Bk. 3, pg. 84



Signed by Gerald W. Carlson Date 12-22-93
Surveyor's Michigan License No. 24589

Record No. 324

#1883
\$9.00
\$100.00
B...

Part "A" Continued:

1978 - Joe Wasie recorded a found 1" iron pin referenced by:

8" Birch	N52°E	17.84'
6" Maple	S67°W	22.28'
3" Pine	S10°W	22.27'

L1 RC, Pg. 263

1981 - G. Carlson recorded a 3/4" iron peg 6" high referenced by:

9" W. Pine	N47°W	9.32'
8" W. Birch	N41°E	18.84'
4" R. Pine	S01°W	22.29'
9" Oak	S58°W	22.28'

L4 RC, Pg. 174

The 1978 and 1981 references were to the incorrect iron pin noted in the 1936 MCRC F.B. 727.

1988 - G. Carlson Recorded a found 5/8" iron peg and remains of J. Pine NBT's referenced by the Marquette County Road Commission in 1936 referenced by:

9" Maple	N81°W	10.03'
12" R. Pine	S32°E	29.00'
5" Maple	S54°E	15.55'
18" R. Pine	N00°E	25.91'

L5 RC, Pg. 149

The 1988 G. Carlson corner is the circ. iron pin noted in the 1936 MCRC notes and falls 1.02'E. and 1.36'N. of calculated position using present day methods.