

1893

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300  
SHEET NO. : 1-323  
For corners in

Located In: MARQUETTE (County) Corner Code ##

1. Public Land Survey	T <u>49N</u> R <u>25W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORDING  
MARQUETTE COUNTY MICHIGAN  
1993 DEC 22 PM 4: 14  
Liber 1 R.C. Page 15  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13: South Quarter Corner Section 33. 1845: William A. 1936 - MCRC field book #727 indicates a found squared Cedar Burt's original survey notes describe the corner monument post correctly set from Yellow Pine 4 N12W 13 1 which is as a wood post referenced by:  
 4" Y. Pine N12W, 13 1  
 4" Spruce N54E, 11 1  
 now a stub about 5' high. Markings plain and distinct. Spruce 4 N54E 11 1 has disappeared. Set circular iron pin S12E 8.7 from Yellow Pine B.T. set new B.T.'s:  
 6" Spruce S75E 16.6 ft. 10" White Pine S85W 4.8 ft.  
 There is a ledge a few ft. North of this corner on South edge of Cranberry and Spruce swamp. (See reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron inside the 1 1/2" iron pipe replaced with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
 19" White Pine S80W 5.28 ft. Wasie and Carlson NBT.  
 9" Spruce N23E 12.06 ft. Wasie NBT Pine.  
 10" Red Pine N61E 27.42 ft. Carlson NBT.  
 20" White Pine S51E 54.95 ft. Carlson NBT.  
 1.65' above ground, left existing iron rod, pipe and old wood post lying next to the new monument  
 Bk. 3, Pg. 78



Signed by: Gerald W. Carlson Date 12-22-93  
 Surveyor's Michigan License No. 24589

Record No. 323

At 28 1/2  
#900  
11/10/1936

Part "A" Continued:

There is also a boulder about 5 ft. diameter broken and opened into a cup shape S60E 4' from 1/4 corner. October 14, 1936.

1978 - Joe Wasie found a 3/4' iron pin in pipe - this corner also noted in Marquette County Road Commission records referenced by:

14" Pine	S75W	5.50 ft.
7" Pine	N20E	12.00 ft.
4" Birch	S45E	12.25 ft.

L1 RC, Pg. 263

1988 - G. Carlson found a 5/8" iron inside a 1 1/2" iron pipe 2.5 ft. high, 2.5 ft. above ground and the cup shape rock referred to in the Marquette County Road Commission notes referenced by:

18" White Pine	S81W	5.27 ft.
10" Red Pine	N62E	27.54 ft.
20" White Pine	N51E	55.08 ft.
14" Red Pine	N31W	62.12 ft.

Centerline cup shaped rock

L5 RC, Pg. 149