

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------------------|-------|
| 1. Public Land Survey | T <u>49N</u> R <u>28W</u> | J11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>35</u> T <u>49N</u> R <u>28W</u> | 3 |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

3 Jan 31 2002
 J11 Jan 30 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (J11) Quarter corner common to Sections 26-35. 1999: Remonumented and recorded by George M. Platz PS 38121. Recorded in Liber 6 of LCRCs, Page 187, Marquette County Records.
 (3-Sec. 35) North 1/16 corner between Sections 34-35. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J11) Mr. Platz's rebar was found lying on the surface of the ground at the corner position. Recovered the four 1977 witnesses noted on the the 1999 recordation, which Mr. Platz describes as having been made by Wm. F. Robey, PS and of which he says there was no evidence. Mr. Robey's S52W is now a windthrow and his N68W a cut stump but the two others are in good condition. Mr. Platz used three of Mr. Robey's trees as new witnesses. Mr. Platz's 1999 description of the witnesses in Part C of his record is not correct in all particulars and they are redescribed below. Both the Roby and Platz positions are one and the same proportionate position described on the 1999 record. I accept the position as a careful and faithful reestablishment of the position of the corner and at record bearing and distance from the 1977 and 1999 witnesses drive a 8" section of 1"ID iron pipe into the rotting bedrock and the recovered 1/2"x18" rebar inside the pipe.
 (3-Sec. 35) Established the corner midway and on a line of mean true bearing between Section corner 1311.99' north and Quarter corner 1311.99' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J11) Set 1/2" rebar inside a 1"IDx8" I. pipe. Found the following witnesses: 8" Maple N50E 22.64' PK/tag 38121 S. face 8" Balsam S89E 17.95' do 7" B. Spruce S27E 8.89' old PK E. face 4" Maple West 20.45' set PK/MDNR tag Bearings are magnetic. Distances horizontal.	(3) Set 1"IDx32" I. pipe with 4" alum. MDNR cap. Blazed and scribed: 10" W. Spruce N30E 13.7' "1/16S 8T" 11" Ash S82E 21.9' do 6" Y. Birch S48W 35.6' do 15" Y. Birch N31W 21.3' do Set squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 3/25/02