

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|------|-------|-------|
| 1. Public Land Survey | T | R | |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S 35 | T 49N | R 28W |
| | S 35 | T 49N | R 28W |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jan 30 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:**
 (4-Sec. 35) Northwest 1/16 corner, Section 35. Not established in the original survey. Found no subsequent record.
 (5-Sec. 35) North 1/16 corner, Section 35. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (4-Sec. 35) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the corner thus established, I found a 1/2" rebar with plastic cap #38121, not of record, N87E 0.64' distant, which I did not accept for the corner. According to my calculations, the 1/2" rebar occupies a position derived from a procedurally improper subdivision of this section.
 (5-Sec. 35) Established the corner midway and on a straight line between Center of Section 1310.12' South and Quarter corner 1310.12' North. From the position thus established, I found a 1/2" rebar with plastic cap #38121, not of record, N76E 1.24' distant which I did not accept for the corner. According to my calculations, this rebar occupies a position derived from a procedurally improper subdivision of this section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (4) Set 1"IDx32" I. pipe with 4" alum. MDNR cap. Blazed and scribed:
11" Spruce North 15.6' "1/16S BT"
9" Spruce S62E 13.4' do
15" Cedar S69W 38.3' do
8" Spruce N61W 18.7' do
Set squared cedar post adjacent.
Bearings are magnetic. Distances are to notch in lower blaze. | (5) Set 1"IDx32" I. Pipe with 4" alum. MDNR cap. Blazed and scribed:
8" Maple N56W 16.8' "1/16S BT"
8" Maple N17E 25.4' do
6" Sugar S80E 24.9' do
10" Sugar S03W 10.4' do
Squared a 10" Y. Birch S32W 1.0' to center of tree. Bearings are magnetic. Distances to notch in lower blaze. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 3/25/02