

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette

(County)

Located In:

Corner Code #

1. Public Land Survey

T 49N R 28W

I13

T 49N R 28W

J13

T R

T R

2. Property Controlling in Section

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jan 30 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (I13) Section corner common to Sections 34-35 T49N-R28W and Sections 2-3 T48N-R28W. 1977: Remonumented by D.B.Babbitt, RLS and recorded with T48N-R28W LCRCs. Marquette Co. Records. Found iron rod as described in old records at the Marquette Co. Rd. Comm. office - they say "set from original bearing tree" - a maple stump is in place for N.E. O.B.T. - no marks (very rotten). 1" pipe with 4" aluminum cap. Tw. stem of Bl. Cherry N13E 26.25', 7" Maple N48E 21.0', 17" Maple S65E 9.7', 5" Maple S60W 24.8'.
 (J13) Quarter corner common to Section 35 T49N-R28W and Section 2 T48N-R28W. 1977: Reestablished by single proportionate measurement between I13 and K13 by D.B.Babbitt and recorded in T48N-R28W LCRCs, Marquette County Records. 1" pipe with 4" aluminum cap. 4" W.Birch N30W 64.6', 6" W.Birch N85W 35.2', 12" J.Pine N78E 40.1', 12" Spruce S47E 35.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I13) Recovered the 1977 monument as described, in good condition, and at record bearing and distance from the 1977 accessories. The 1977 N13E B.Cherry and N48E Maple are now down. The other two are in good condition. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(J13) Recovered the 1977 monument as described, in good condition, under the surface of a N-S graded road (east side), and at record bearing and distance from the 1977 accessories. The N78E J.Pine and S47E Spruce are dead and down. The other two witnesses are in good condition. My measurements east and west to adjacent corners confirm that this monument is located according to the intent of the 1977 record and it is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I13) Found 1" ID I.Pipe with 4" alum.

MDNR cap. Blazed and scribed:

6" Sugar S16E 12.5' S2 NBT

5" Sugar N55E 26.4' S35 NBT

The 1977 wits:

17" Sugar S62E 9.7' overgrown blazes

6" Sugar S67W 24.8' do

Squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.

(J13) Found 1" ID I.Pipe with 4" alum.

MDNR cap. Blazed and scribed:

18" Oak N55E 72.4' 1/4S NBT

4" Sugar S21E 44.2' do

the 1977 wits:

9" W.Birch N80W 35.2' overgrown blazes

7" W.Birch N24W 64.6' do

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski

Date 3/25/02

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1985