

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

(County)

Located In: Corner Code #

1. Public Land Survey	T <u>50N</u> R <u>27W</u>	<u>15</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous	S ___ T ___ R ___	___
Property in Sec.	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 30 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (I5) Corner common to Sections 10-11-14-15. 1852- Established by Abner B. Wood: North true line between Secs. 14-15...40.00 Set quarter Section post...47.25 Stream 6 C-E...80.00 Set Post corner of Sections 10-11-14-15. Fir 8 N78E 30, Sugar 5 N32W 13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I5) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between Quarter corner 2630.22' North (40.00 ch. US), Quarter corner 2634.15' East (39.98 ch. US), Section corner 10544.58' West (160.04 ch. US), and stream crossing noted above 2153.57' South (32.75 ch. US).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I5) Set a 1"IDx11" I.pipe with 4" alum. MDNR cap, driven into a crevice in the bedrock, made firm with small rock and portland cement concrete. Blazed, scribed, and set measuring nails in:

10" W.Pine N10E 46.8' "S11 NBT"
 5" Oak N74E 31.4' do
 6" Sugar S66W 30.5' "S15 NBT"
 Twin 10" Oak N77W 8.8' "S10 NBT"

Bearings are magnetic. Dist. to nail with tag.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986



Date 5/14/03