

JUL 03 2000

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1996 NOV 22 AM 11:05

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

Located In: Corner Code #

1. Public Land Survey	T 50N R 28W	(A1)
	T 50N R 29W	MI
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Patricia A. Mosley
REGISTER OF DEEDS

LIBER R1 PAGE 307
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 27 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A1) Northwest corner of T50N-R28W and Northeast corner of T50N-R29W. Corner established in 1846 by Austin Burt: " 74.90 Intersect 5th Correction Line 0.96 west of quarter section corner on South Side of Section 33...Set sugar post. Lynn 10 S15W 6, 8. Ash 10 S64E 44." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A1) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner at record distance west of the quarter section corner on the south side of Section 33 T51N-R28W, and on a straight line between the quarter corner and the Standard corner between Sections 32-33 T51N-R28W. At the position for the corner, I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Laury J. Bussard
DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A1) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:

- 10" Sugar N40E 23.2' "S33 NBT"
- 5" Sugar S86E 15.5' "S6 NBT"
- 4" Sugar N25W 16.3' "S33 NBT"
- 4" Sugar S43W 19.0' "S1 NBT"

A 14" dead Y. Birch with a location poster affixed bears S70E 12.5'. Bearings are magnetic.

MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

New bearing trees are marked with a BH blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11-5-96

For the Michigan Department of Natural Resources - Forest Management Division