

REMA

JUL 03 2000

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1996 NOV 22 AM 11: 06

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 28W C1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Patricia A. Manley REGISTER OF DEEDS

LIBER R1 PAGE 311 Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Sep 06 1995

I, Stephan J. Szyszkoski, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of row 1 and column C.

A. Description of original monument and accessories and/or subsequent restoration:

(C1) Closing corner common to Sections 5-6. Corner established in 1852 by Abner B. Wood: "74.54 Intersect North Boundary of township and set post 124 links west of qr. Sec. corner on south side of Section 34 T51N-R28W. Sugar 14 S40E 23, Spruce 10 S55W 42". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C1) Original post and accessories not recovered. Reestablished the corner on a straight line between standard corners at the south quarter corner Section 34 T51N-R28W and the Southwest corner of Section 34 T51N-R28W, and at record distance west of the quarter corner. At the position for the corner, I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The corner falls in the north side of a trail road leading westerly. Buried the monument to 4" below the surface.

RATIFIED BY PEER GROUP P.A. 315 OF 1990

Larry J. Bussone DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C1) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:

- 4" Sugar N20E 42.6' "S34 NBT"
20" Sugar N55W 21.5' "S34 NBT"
7" Sugar S44W 42.0' "S6 NBT"
5" Sugar S47E 53.1' "S5 NBT"

Bearings are magnetic.

MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

New bearing trees are marked with a 8H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by Stephan J. Szyszkoski Surveyor's Michigan License No. 33986

Date 11-5-96

For the Michigan Department of Natural Resources - Forest Management Division