

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**Marquette**  
 (County)

Located in:

Corner Code -#

1	Public Land Survey	T50M	R7W	L5
		T	R	M4
		T	R	M5
		T	R	
2	Property Controlling in Section	S12	T	R
		S	T	R
3	Miscellaneous Property in Sec	S	T	R
		S	T	R

Register of Deeds Stamp & File Number

4 Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	8	8	4			3		2				
3													
4	7	8	9				10		11			12	
5													
6	18	17	16				15		14			13	
7													
8	19	20	21				22		23			24	
9													
10	30	29	28				27		26			25	
11													
12	31	32	33				34		35			36	
13													

I, **Keith Sackett**, in a field survey on **September 11**, 19 **89**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A Description of original monument and accessories and/or subsequent restoration:**

<b>L5</b>	<b>M4</b>	<b>M5</b>	<b>7</b>
Original monument and accessories not found.	Original monument and accessories not found.	Original monument and accessories not found. Found 1" x unknown length iron pipe in county road.	Not set on original survey nor subsequently, apparently.

**B Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

<b>L5</b>	<b>M4</b>	<b>M5</b>	<b>7</b>
Restored midway and on line.	Restored midway and on line.	Restored at 1" iron pipe by unknown length buried in road. Pipe fits very good north and south and west. Line tree stump south fits exact distance.	Established midway and on line.

**C Description of monument for corner and accessories established to perpetuate locating the position of the corner**

<b>L5</b>	<b>M4</b>	<b>M5</b>	
Set 1" 10 x 36" IP with 4" aluminum cap.	Set 1" 10 x 32" IP with 4" aluminum cap.	1" 10 by unknown length iron pipe.	Set 1" 10 x 32" IP with 4" aluminum cap.
12" jack pine S15W 7.9' 1/4S, NBT	7" white pine S12W 5.7' 1/4S, NBT	11" jack pine S02E 26.4' S18, NBT w/Longyear tag.	10" white birch N72W 4.2' 1/16S, BT
10" jack pine N07E 11.5' 1/4S, NBT	7" white pine N40E 19.1' 1/4S, NBT with Longyear Tag	11" jack pine N11W 53.9' S12, NBT	12" jack pine S36E 17.9' 1/16S, BT
9" jack pine S53E 20.4' 1/4S, NBT	8" white pine N72W 14.6' 1/4S, NBT	10" jack pine S48W 23.6' S13, NBT	4" jack pine N52E 9.9' 1/16S, BT

Signed by Keith Sackett Date \_\_\_\_\_

Surveyor's Michigan License No. \_\_\_\_\_

19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 28 1971  
 REVISED MAY 14, 1978  
 REVISED JAN. 1983

9-21-89