

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

(County)

Located In:

Corner Code #/

1	Public Land Survey	T5CN	R7W	K4	_____
		T	R	K5	_____
		T	R	_____	_____
		T	R	_____	_____
2	Property Controlling in Section	S2	T	R	10
		S	T	R	15
3	Miscellaneous Property in Sec	S	T	R	_____
		S	T	R	_____

Register of Deeds Stamp & File Number

4 Lot No _____ Recorded Plat _____
5 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	9	10	11	12	13	14	15	16	17	18	19	20
3													
4													
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Keith Sackett, in a field survey on September 11, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration

K4	K5	10	15
Original monument and accessories not found. Found 2" iron & old NRT by unknown person. Fits good with other corners.	Original monument and accessories not found. Found pipe which fits other corners and land calls.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K4	K5	10	15
Restored at 2" iron pipe.	Restored at pipe.	Established midway and on line.	Established midway and on line.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner

K4	K5	10	15
2" iron monument, 8" jack pine N57E 4.4' 1/4S, NRT	1" ID by unknown length iron pipe- 9" jack pine N10W 5.5' S11, NRT	Set 1" 10 x 32" IP with 4" aluminum cap, 3" spruce S80E 10.4' 1/16S, BT 12" jack pine S81W 17.1' 1/16S, BT	Set 1" 10 x 36" IP with 4" aluminum cap, 4" spruce N53E 19.1' 1/16S, BT 4" spruce S48W 3.9' 1/16S, BT 4" jack pine S72E 24.3' 1/16S, BT
7" jack pine S04E 4.7' 1/4S, NRT	12" jack pine S83W 13.9' S14, NRT	4" maple N20W 19.6' 1/16S, BT	
6" jack pine N80W 12.1' 1/4S, NRT	9" jack pine S32E 15.6' S13, NRT		
4" jack pine S68E 3.8' squared	4" jack pine squared S05W 3.0'		

Signed by *Keith Sackett*

Date _____

Surveyor's Michigan License No. _____

1989

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983