

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Marquette
 (County)

Located In: Corner Code #1

1	Public Land Survey	T 50N	R 27W	L3
		T	R	M3
		T	R	
		T	R	
2	Property Controlling in Section	S 12	T R	1
		S	T R	3
3	Miscellaneous Property in Sec	S	T R	
		S	T R	

Register of Deeds Stamp & File Number

4 Lot No. , Recorded Plat
 5 Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith Sackett, in a field survey on September 11, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

L3	M3	1	3
Found stub with old chopping which matches original BT bearing and distance, and species.	Found pine stub with blazes and scribing found 1" ID pipe set from stub. Also pine stump that matches other B.T.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner.

L3	M3	1	3
Restored from stub.	Restored at pipe.	Established midway and on line.	Established midway and on line.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner

L3	M3	1	3
Set 1" ID x 32" IP with 4" aluminum cap.	1" ID x unknown length iron pipe.	Set 1" ID x 32" IP with 4" aluminum cap.	Set 1" ID x 32" IP with 4" aluminum cap.
6" Jack pine S20E 17.4' 1/16S, BT	7" white pine S75W 32.6' S12, NPI	7" Jack pine N84E 14.0' 1/16S, BT	10" Jack pine N19E 4.9' 1/16S, BT
7" Jack pine S35W 17.5' 1/16S, BT	6" white pine S65E 22.2' E7, NFI	9" Jack pine N08E 7.6' 1/16S, BT	7" Jack pine N54W 4.2' 1/16S, BT
7" Jack pine N60E 9.4' 1/16S, BT	11" Jack pine N65W 9.0' S1, NFI	9" Jack pine S32W 4.2' 1/16S, BT	7" Jack pine S17W 28.7' 1/16S, BT
8" Jack pine squared N65E 2.3'			8" Jack pine squared west

Signed by

Keith Sackett

Date

9-21-89

Surveyor's Michigan License No.

19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983