

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
RECEIVED FOR RECORD

1996 NOV 22 AM 11:07

Patricia A. Monley
REGISTER OF DEEDS

For corners in

Marquette

(County)

Located In:

Corner Code #

1. Public Land Survey

T 50N R 29W

11

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sep 28 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(1) Closing corner common to Sections 2-3. Corner established in 1852 by Abner B. Wood: "75.18 Intersect North boundary of township and set post 168 links W. of qr. corner on S. side of Section 31 T51N-R28W. Hemlock 6 S42W 7, Fir 8 S73E 65". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on a straight line between the South 1/4 corner Sec. 31 T51N-R28W, and the Southwest corner of T51N-R28W and at record distance west of the 1/4 corner. At the position for the corner, I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner, I found a forester's old squared cedar post S06W 11.6' with a 24" cedar signature tree facing it. I removed the post and placed it adjacent to the monumented corner. I also found a 24" hemlock, with old blazes on 4 sides and with a Mead location poster affixed, S14W 4 ft. from the corner.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bassal
DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1" pipe with 4" MDNR cap. MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

Blazed and scribed the following new bearing trees:
14" Hemlock S21E 3.5' "S2 NBT"
10" Sugar N41E 14.5' "S31 NBT"
8" Maple N71W 19.3' "S31 NBT"
8" Maple S28W 35.6' "S3 NBT"

New bearing trees are marked with a 8H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by *Stephan J. Szyszkoski*
Surveyor's Michigan License No. 33986

Date 11-5-96

For the Michigan Department of Natural Resources - Forest Management Division

LIBER 1 PAGE 315
Register of Deeds Stamp & File Number