

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
RECEIVED FOR RECORD

1996 NOV 22 AM 11: 06

Patricia A. Monberg
REGISTER OF DEEDS

For corners in
Marquette

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------|-------|
| 1. Public Land Survey | T 50N R 29W | J1 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

LIBER 1 PAGE 313
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Dec 06 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J1) North Quarter corner of Section 2. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J1) Found no evidence of prior monumentation at the corner position. Established the corner midway between closing corners 2640.65 ft. east and west and on the 5th Correction Line between the Standard Corner common to Sections 31-32 T51N-R28W and the South 1/4 corner of Section 31 T51N-R28W. At the position for the corner, I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR cap, appropriately stamped.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Busome
DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J1) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following bearing trees:

- 16" Sugar N71E 49.3 "1/4S BT"
- 7" Sugar S55E 36.2' "1/4S BT"
- 18" Hemlock S55W 15.5' "1/4S NBT"
- 7" Sugar N50W 27.5' "1/4S NBT"

An MDNR monument at the Standard Corner common to Sections 31-32 T51N-R28W is 89.1 ft. east. Bearings are magnetic.

MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

New bearing trees are marked with a 8H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by *Stephan J. Szyszkoski*
Surveyor's Michigan License No. 33986

Date 11-5-96

For the Michigan Department of Natural Resources - Forest Management Division