

REV

JUL 03 2000

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1996 NOV 22 AM 11:05

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Patricia R. Mansley REGISTER OF DEEDS

For corners in Marquette

Located In:

Corner Code #

Table with 3 columns: Section, Located In (T, S, R), and Corner Code #. Includes handwritten entries like 'A2' and 'MZ'.

LIBER R1 PAGE 308 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

Sep 27 1995

I, Stephan J. Szyszkoski, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Cell (2,6) contains a dot.

A. Description of original monument and accessories and/or subsequent restoration:

(A2) Quarter corner common to Section 6 T50N-R28W and Section 1 T50N-R29W. Corner established in 1846 by Austin Burt: "40.00 Set maple post Qr. Sec. Cor. Hemlock 32 S84E 34, W. Birch 14 N71W 17". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A2) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on a straight line between Section corner 2619.47' south and closing corner 2285.48' north, being 40.00 chains, proportionate to the original record, north of the section corner. At the position for the corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Signature of Larry J. Bussome DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A2) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:

- 12" Sugar N20E 9.2' "1/4S NBT"
9" Oak N36W 20.9' "1/4S NBT"
5" Hemlock S39E 23.8' "1/4S NBT"
12" Hemlock S61W 27.8' "1/4S NBT"

MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

New bearing trees are marked with a 8H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.

A 16" Cedar, blazed, with signatures and a location poster, was found facing the corner, N21E 21.2'. Bearings are magnetic.

Signed by Stephan J. Szyszkoski Surveyor's Michigan License No. 33986

Date 11-5-96



For the Michigan Department of Natural Resources - Forest Management Division